

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL
ARTS, SECTOR-6, ROHTAK
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby **re-invited** for and on behalf of Registrar DLCSUPVA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 11/4/25 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Repairing F.C. Office of FTV Department and providing and fixing of toilet doors in Girls Hostel, DLCSUPVA, Rohtak. (Details of scope of work attached with the notice)	56,206/-	30 Days

- SJ -
SDE (Civil)/E.O.

No. DLCSUPVA/UEW/ Eo 10147-51

Dated: 4/4/25

Copy of the above is forwarded to the following for information and necessary action:-

- ✓ 1. Accounts Officer/ Nominee
2. SDE (C)/E.O.
3. Supdtt. (UEW)
4. JE (C)
5. IT Cell to upload on website please.


SDE (Civil)/E.O.

DNIQ for repairing F.C. Office of FTV Department and providing and fixing of toilet doors in Girls Hostel, DLCSUPVA, Rohtak.
Approx. Amount: - Rs. 56,206/- (I/C GST)

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor/ Supplier	Amount
1.	HSR 11.58: - Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material, labour charges, scaffolding, sundries etc. complete.	11.66	Sqm		
2.	HSR 30.25.1: - Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade: Old work (one or more coats)	50.90	Sqm		
3.	HSR 30.16.1: - Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1 :4 (1 cement : 4 fine sand)	11.66	Sqm		
4.	HSR 11.76:- Preparation of ply wood surface for painting including sand papering the surface and applying filling with approved quality filler consisting of white lead, linseed oil, varnish and chalk mitti including finishing the surface to required finish complete.	57.21	Sqm		
5.	HSR 30.32.1:- French spirit polishing: One or more coats on old work	32.11	Sqm		
6.	HSR 10.104:- Mirror polishing on marble work/Granite work/stone work wherever required to give high gloss finish complete	27.46	Sqm		
7.	HSR 12.36.1: Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well-matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary	12.54	Sqm		

	screws.				
8.	HSR 11.78: Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade	41.04	Sqm		
9.	HSR 11.77: Applying pink primer or aluminium priming coat on wood work including preparation of surface, Knotting and stopping etc.	30.11	Sqm		
Total Amount (Including GST)					

Time Limit: 30 Days

Note:-

1. The work should be executed strictly as per the specification mentioned in DNIQ
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.