

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL  
ARTS, SECTOR-6, ROHTAK  
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUPVA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 23/5/25 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Repairing and whitewashing of flat no. A-104 & 202 in 1900 sft and flat B-203 houses in Residential Complex, DLCSUPVA, Rohtak. (Details of scope of work attached with the notice)	89,386/-	21 Days

  
SDE (Civil)/E.O.

No. DLCSUPVA/UEW/ 229 - 33

Dated: 16/5/25

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (C)/E.O.
3. Supdt. (UEW)
4. JE (C)
5. IT Cell to upload on website please.

  
SDE (Civil)/E.O.  


**DNIQ for repairing and whitewashing of flat no. A-104 & 202 in 1900 sft and flat B-203 houses in Residential Complex, DLCSUPVA, Rohtak.**  
**Approx. Amount: - Rs. 89,386/- (I/C GST)**

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor/ Supplier	Amount
1.	<b>HSR 30.27.1:-</b> Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work.	309.47	Sqm		
2.	<b>HSR 11.58:-</b> Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material, labour charges, scaffolding, sundries etc. complete.	146.88	Sqm		
3.	<b>HSR 11.64.1:-</b> Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade: New work (two or more coats) over and including water thinnable priming coat with cement primer	155.00	Sqm		
4.	<b>HSR 10.73:-</b> Providing and fixing ceramic & Glazed tiles/ vitrified tiles/ of any size of approved make in floors / dados, laid in any pattern as specified over base of 3 mm thick adhesive of reputed brands as per IS specification 15477-2004 using 5 Kg. adhesive per sqm area of tiles and jointed with white cement slurry mixed with pigment to match the shade of tiles.	13.53	Sqm		
5.	<b>HSR 9.46.1:-</b> Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS: 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia. x 50mm long with 6mm dia. bolts, other flange of cleat fixed to the angle hangers of 25x1 O x 0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia. x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling	17.84	Sqm		

	fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering up to 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I):2011 (Board with BIS certification marks)				
6.	HSR 11.1.1: 6 mm cement plaster of mix, 1 :3 (1 cement : 3 fine sand)	115.88	Sqm		
7.	HSR 11.123.1: - Wall painting with (bio grade) plastic emulsion paint of approved brand and manufacturer to give an even shade (two or more coats) Generally used in hospital buildings etc. complete as per Specifications	115.88	Sqm		
8.	HSR 10.73:- Providing and fixing ceramic & Glazed tiles/ vitrified tiles/ of any size of approved make in floors / dados, laid in any pattern as specified over base of 3 mm thick adhesive of reputed brands as per IS specification 15477-2004 using 5 Kg. adhesive per sqm area of tiles and jointed with white cement slurry mixed with pigment to match the shade of tiles.	3.11	Sqm		
Total Amount (Including GST)					

**Time Limit: 21 Days**

**Note:-**

1. The work should be executed strictly as per the specification mentioned in DNIQ
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.